Vaikunt Mehta National Institute of Cooperative Management,

Near Ganeshkhind Road, Pune University Chowk, Pune – 411007.

No. VM/BOCT/Miscell./2022-23/ Date: 01.06.2022

Request for Quotation (RFQ)

for attaching nearby toilet to Ladies Rest Room in the Ground Floor of VAMNICOM Bhavan at VAMNICOM, Pune

****

The Vaikunth Mehta National Institute of Cooperative Management (VAMNICOM), Pune invites quotations from reputed local agencies to attach a nearby toilet to ladies rest room at ground floor of VAMNICOM Bhavan building. The quotation in the prescribed format printed on **letter head** shall be submitted in **sealed covers** on or before **16th JUNE, 2022** to the **Office of Registrar, VAMNICOM, Pune**. The covers should be **super-scribed** with name of work i.e. "**Attaching nearby toilet to Ladies Rest Room in the Ground Floor of VAMNICOM Bhavan at VAMNICOM, Pune**". The quotation shall be opened on **17th JUNE, 2022** at **11:00 AM** at VAMNICOM Bhavan.

Terms & Conditions

1. Name, address and contact details of the Agency in Annexure – A.
2. A copy of the GST Registration Certificate.
3. The copy of clients and list of ongoing/ executed work orders and performance certificates. The annual turnover of the agency shall not be less than five lakhs.
4. Latest copies of acknowledgments of GST payment of last three months.
5. All rates shall be quoted in the prescribed format only (refer Annexure – B). Quotes different from prescribed format shall be liable for rejection.
6. Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their quotation.
7. The quotation shall include all labour, tools, and for the entire execution of the works.
8. In case of any damage to the Institute's property, the VAMNICOM may deduct such damage charges from the bill of the Agency.
9. The Agency shall complete the repair work within 20 days after receiving Work Order.
10. The VAMNICOM reserves the right to cancel this RFE at any moment without giving any reasons.
11. Quantities are taken as per details provided, any deviations in actual will be paid as per the actual measurement and rate quoated by the successful bidder.
12. The rates must include all the taxes.
13. Electricity and Water will be provided by the Institute.

V. Sudhir 01/06/2022

Registrar

Vaikunth Mehta National Institute
of Cooperative Management, Pune – 411007.

Annexure – A

"We, M/s _____, hereby, undertake that we have submitted the above rates after examining the site and its surroundings and we also agree to all the terms and conditions of the Institute mentioned above".

Name of Agency : M/s _____

Address : _____

_____

Contact No. : _____

Email : _____

GST No. : _____

(Signature with seal of agency)

Request for Quotation (RFQ) for attaching a nearby toilet to the Ladies Rest Room at VAMNICOM, Pune

Ref:- VM/BOCT/Miscell./ Date: 01.06.2022

Sr No	Description	Qty	Unit	Unit Price	Total Price
1	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions	1	Each		
2	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead	1	Each		
3	Demolishing brickwork manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per directions	0.53	Cum		
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete	8	Mtr		
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.	1.70	Sqm		
6	15 mm cement plaster on rough side of single or a half brick wall of mix: 1:5 or 1:6	3.95	Sqm		

7	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand)	5.80	Rmt		
	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry	18	Sqm		
8	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	2.2	Sqm		
9	Providing and fixing Hand shower (Health faucet) of approved make with 8 mm dia. and minimum 1.00 metre long flexible tube in chrome finish and wall hook with all necessary fittings etc.,	1	Each		
10	Providing and fixing 2 way angle cock with all necessary fittings etc.,	1	Each		

11	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	1	Each		
12	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	1	Each		
13	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
13.1	15mm nominal bore	1	Each		
15	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
15.1	For thickness of tiles 10 mm to 25 mm	15	Sqm		
16	Removing existing PVC door and Re fixing same another place with necessary screw fitting etc.	1	Job		
				Total	

"We, M/s _____, hereby, undertake that we have submitted the above rates after examining the site and its surroundings and we also agree to all the terms and conditions of the Institute mentioned in the RFQ".

Authorised Signatory